



# Heat Exchanger

**HX-400D**

## Features:

- Frame-mounted shell and tube heat exchanger
- Steam to domestic hot water transfer
- Pre-installed steam valving ready for use

## General Information

<b>Rental Category</b>	Heat Exchanger
<b>Unit Design</b>	Skid-mounted
<b>Heat Exchanger Design</b>	Shell and Tube
<b>Use Type</b>	Steam – Domestic Hot Water

## Specifications and Requirements

<b>Usable Surface Area</b>	148 ft <sup>2</sup> (13.7 m <sup>2</sup> )
<b>Design Pressure – Shell</b>	150 PSIG (10.3 BARG)
<b>Feedwater Output Flow</b>	150 PSIG (10.3 BARG)
<b>Max Flow (Tube)</b>	400 GPM (1,510 LPM)
<b>Electricity</b>	120 V / 1 Phase / 20 A @ 60 Hz

## Connections

<b>Steam (Input)</b>	4" 150# FLG
<b>Condensate (Output)</b>	2" NPT
<b>Water Supply (Output)</b>	4" 150# FLG
<b>Water Supply (Input)</b>	4" 150# FLG

## Dimensions

<b>Overall Length</b>	07' 08" (2.3 M)
<b>Overall Width</b>	06' 01" (1.9 M)
<b>Overall Height</b>	02' 10" (0.9 M)
<b>Shipping Weight</b>	2,500 LBS (1,135 KGS)

Last updated on: 17-Dec-24



**Atlas Copco  
Rental**  
Making Agility Count

**Atlas Copco Rental**

[www.atlascopcorental.com](http://www.atlascopcorental.com)

Subject to change without prior notice. Information is for guidance only. Please contact your nearest Rental office for detailed application advice.